



Tentative Interim Amendment

NFPA 13R

Standard for the Installation of Sprinkler Systems in Residential Occupancies up to and Including Four Stories in Height

2010 Edition

Reference: 4.7 and 5.4.3

TIA 10-2

(SC 11-3-5/TIA Log #1013)

Pursuant to Section 5 of the NFPA Regulations Governing Committee Projects, the National Fire Protection Association has issued the following Tentative Interim Amendment to NFPA 13R, *Standard for the Installation of Sprinkler Systems in Residential Occupancies up to and Including Four Stories in Height*, 2010 edition. The TIA was processed by the Technical Committee on Residential Sprinkler Systems and the Technical Correlating Committee on Automatic Sprinkler Systems, and was issued by the Standards Council on March 1, 2011, with an effective date of March 21, 2011.

A Tentative Interim Amendment is tentative because it has not been processed through the entire standards-making procedures. It is interim because it is effective only between editions of the standard. A TIA automatically becomes a proposal of the proponent for the next edition of the standard; as such, it then is subject to all of the procedures of the standards-making process.

1. *Delete Section 4.7, that was language added by the issuance of TIA No. 10-1 (Log #995) in August of 2010.*
2. *Delete new 5.4.3, that was language added by the issuance of TIA No. 10-1 (Log #995) in August of 2010.*
3. *Revise 5.4.4 to 5.4.3, that was language added by the issuance of TIA No. 10-1 (Log #995) in August of 2010 to read as follows:*

5.4.3 Where antifreeze systems, dry pipe systems, and preaction systems are installed, they shall be installed in accordance with NFPA 13.

Issue Date: March 1, 2011

Effective Date: March 21, 2011

(Note: For further information on NFPA Codes and Standards, please see www.nfpa.org/codelist)