



Tentative Interim Amendment

NFPA 110

Standard for Emergency and Standby Power Systems

2010 Edition

Reference: 7.13.4.1.3(a) and 7.13.4.3.4

TIA 10-1

(SC 09-8-26/TIA Log #965)

Note: Text of the TIA issued and incorporated into the text of 7.13.4.1.3(a) and 7.13.4.3.4 therefore no separate publication is necessary.

1. *Revise Section 7.13.4.1.3 (a) as follows:*

“When the EPSS consists of paralleled EPSs, the quantity of EPSs intended to be operated simultaneously shall be tested simultaneously with the building load for a ~~2-hour period~~ the test period identified in Section 7.13.4.1.3(j).”

2. *Revise Section 7.13.4.3.4 as follows:*

“The data specified in 7.13.4.1.3 (d), (e), (g), (h), and (i) shall be recorded at first load acceptance and every 15 minutes thereafter until the completion of the ~~2-hour~~ test period identified in Section 7.13.4.1.3(j).”

Issue Date: August 6, 2009

Effective Date: August 26, 2009

(Note: For further information on NFPA Codes and Standards, please see www.nfpa.org/codelist)